



(310) 477-1938  
info@thecomplexstudios.com  
2323 Corinth Ave, Los Angeles, CA 90064

## STAGE 2: TECH SHEET

Square Footage: 2436 Sq.Ft.  
Dimension: 58'L x 42"W  
WIFI access point 50 down/25 up  
Controlled and quiet Air Conditioning  
Power: Two 300 amp, 3 Phase with cam lock: 600 amp total  
On-site parking available  
Green Room included / additional rooms available  
Grid height: 18'

180° Infinity Wall Cyc (Default color is green):

Dimensions: 38'8"W x 23'8" Left wall x 15'4" Right Wall  
Default color of cyc is Green

Colors: Gray, White, Black - (Paint and Labor fee apply-12 hour notice),  
Chroma Key Blue (Paint and Labor fee apply with 36hrs notice)

Built-in Set: Non-movable set is built on the edges of stage 2. (fee applies)  
Platform is removable and Ceiling platform can be lowered and raised.

Lighting:

Pre-lit Green Screen cyc with 3 space lights  
ETC Express 48/96 lighting board  
In-house Lighting equipment available for rent

Ethernet:

2 public IP ports, 1Gbps up/down, (Fee applies, router not included,  
we recommend a 1Gbps router with multiple ports to create a private network)  
1 PCR 1 Director tie line  
Stage tie-lines: 4 tie lines to Right Panel (one is missing and one unknown)  
4 tie lines to Lift Panel

Video: STG2RK1

8 video router inputs / 8 video router outputs  
in-Stage tie-lines: 10 tie lines to the Right box, 10 tie lines to the Left box  
Router input reference: Black Burst or Tri-level Sync  
Router input compatibility: SDI Video Sampling: 4:2:2 and 4:4:4  
HD Format Support: All in-house equipment is setup for 1080i59.94  
1080i50, 1080i59.94, 1080i60  
1080p23.98, 24, 25, 29.97, 30, 50, 59.94, 60  
720p23.98, 24, 25, 29.97, 30, 50, 59.94, 60  
2K Format Support: 2K DCI 23.98p, 2K DCI 24p, 2K DCI 25p  
SD Format Support: 525i29.97 NTSC

Audio: Overhead Speakers

STG2RK1

14 audio tie lines to AudioRM  
4 Microphones to AudioRM  
2 IFBs from AudioRM

Stage 2: Measurements and details

